

土木設計業務シリーズ

造成計画計算 6

Ver 1. X. X

帳票サンプル集

目 次

格子点標高一覧表.....	1
メッシュ土量一覧表（地山）.....	2
メッシュ内運土一覧表（換算）.....	3
ブロック土量一覧表（地山）.....	4
ブロック内運土一覧表（換算）.....	6
ブロック間手動運土一覧表（換算）.....	8
ブロック間自動運土一覧表（換算）.....	10
土質別地山換算土量計算書.....	14
工区間自動運土一覧表（換算）.....	16

※ 帳票は印刷時に印刷項目・項目の大きさ・文字サイズ・用紙サイズなどのカスタマイズが可能です。

※ このサンプルはカスタマイズの一例とお考えください。

格子点標高一覧表

[新規業務] 新規備考

I	J	計 画 高	現 況 高	軟 岩 I	軟 岩 II
6	21	100.45	110.20	106.20	98.80
	22	100.39	121.60	116.20	110.50
	23	100.35	108.40	103.10	99.50
	24	100.38	106.90	100.90	96.40
	26	100.50	103.80	95.80	90.30
7	20	100.40	115.20	108.00	102.90
	21	100.35	122.50	117.80	110.00
	22	100.31	127.10	120.20	113.60
	23	100.26	117.30	111.40	106.20
	24	100.30	113.80	106.90	99.70
	25	100.35	111.60	104.40	98.60
	26	100.40	112.40	101.20	95.00
	27	100.45	109.60	100.50	94.80
8	18	112.95	121.20	112.20	103.60
	19	100.36	117.00	110.30	104.30
	20	100.32	125.20	119.50	114.20
	21	100.27	133.40	129.60	119.20
	22	100.21	122.20	115.80	110.40
	23	100.17	109.10	104.20	101.40
	24	100.21	99.90	96.00	93.20
	25	100.27	100.60	95.00	91.80
	26	100.32	113.60	96.10	91.00
	27	100.37	97.60	93.50	88.40
	28	98.15	92.20	88.30	81.90
	29	89.85	88.50	84.90	79.80
9	17	123.45	131.00	117.90	109.80
	18	112.95	131.80	119.40	111.50
	19	100.27	129.60	122.60	117.00
	20	100.23	127.20	121.90	115.60
	21	100.18	123.80	119.60	112.40
	22	100.14	121.40	115.00	109.70
	23	100.09	112.40	106.40	102.10
	24	100.13	101.20	96.90	92.50
	25	100.18	89.60	86.60	84.50
	26	100.23	90.00	86.00	0.00
	27	100.28	87.60	84.30	80.00
	28	98.05	83.80	78.40	0.00
	29	89.75	80.50	0.00	0.00
	30	76.95	78.00	0.00	0.00
10	18	112.75	122.20	114.80	108.80
	19	100.19	121.30	115.90	111.30
	20	100.15	112.40	108.50	104.80
	21	100.09	111.20	106.80	100.80
	22	100.05	107.60	102.40	99.50
	23	100.00	105.40	100.50	97.90
	24	100.04	93.60	90.30	87.60
	25	100.09	89.40	86.10	83.50
	26	100.15	82.90	0.00	0.00
	27	100.19	79.90	0.00	0.00
	28	97.95	79.10	0.00	0.00
	29	89.55	77.30	0.00	0.00
	30	76.95	76.70	0.00	0.00
11	19	100.11	107.60	104.20	99.60
	20	100.05	100.20	97.60	94.50
	21	100.00	99.60	96.50	91.20

メッシュ土量一覧表（地山）

[新規業務] 新規備考

I	J	土 砂	軟 岩 I	軟 岩 II	切 土 計	盛 土	盛 土 計
5	20	400	575	0	975		
	21	940	1145	1011	3096		
	22	1070	845	1011	2926		
	23	1130	327	0	1457		
	24	600	52	0	652		
	25	330	0	0	330		
	26	330	0	0	330		
6	19	720	510	250	1480		
	20	1590	1865	1215	4670		
	21	2100	2585	3305	7990		
	22	2350	2025	2934	7309		
	23	2410	1507	594	4511		
	24	2010	1117	0	3127		
	25	2170	485	0	2655		
	26	2360	85	0	2445		
	27	910	5	0	915		
7	17	825	0	0	825		
	18	1495	600	394	2489		
	19	1960	1640	2032	5632		
	20	2140	2860	4496	9496		
	21	2180	3020	5206	10406		
	22	2410	2000	3065	7475		
	23	1770	1460	717	3947	31	31
	24	1443	1065	0	2508	31	31
	25	3201	485	0	3686		
	26	3358	85	0	3443	277	277
	27	910	5	0	915	872	872
	28					730	730
	29					135	135
8	16	755	0	0	755		
	17	2820	645	0	3465		
	18	3435	1805	2067	7307		
	19	2470	2320	4992	9782		
	20	1900	2920	6040	10860		
	21	2080	2830	5090	10000		
	22	2370	1780	2299	6449		
	23	1197	710	324	2231	31	31
	24	140	0	0	140	1089	1089
	25	1361	0	0	1361	2081	2081
	26	1328	0	0	1328	2568	2568
	27					3565	3565
	28					3080	3080
	29	105	0	0	105	1060	1060
	30	105	0	0	105		
9	16	755	0	0	755		
	17	2735	850	0	3585		
	18	3220	1870	2784	7874		
	19	2160	2020	4786	8966		
	20	1780	2320	3295	7395		
	21	2020	2085	2249	6354		
	22	2250	1245	1157	4652		
	23	1197	480	201	1878	644	644
	24	107	0	0	107	2771	2771
	25					4875	4875
	26					6045	6045

メッシュ内運土一覧表（換算）

[新規業務] 新規備考

I	J	土 砂	軟 岩 I	軟 岩 II	切 土 計	距離(m)	仕 事 量
7	23	13	12	6	31	10.16	315
7	24	17	14	0	31	10.89	337
7	26	269	8	0	277	9.57	2651
7	27	864	5	0	869	12.11	10524
8	23	16	10	5	31	11.25	348
8	24	133	0	0	133	7.64	1016
8	25	1293	0	0	1293	11.11	14365
8	26	1262	0	0	1262	10.76	13579
8	29	100	0	0	100	10.08	1008
9	23	391	173	80	644	11.82	7613
9	24	102	0	0	102	9.86	1006
9	29	100	0	0	100	11.43	1143
9	30	25	0	0	25	10.00	250
10	20	13	17	10	40	11.25	449
10	21	417	401	37	855	11.41	9755
10	22	960	299	0	1259	10.00	12590
10	23	466	52	0	518	10.71	5548
10	35	62	0	0	62	10.00	620
11	17	43	0	0	43	10.00	430
11	18	323	429	0	752	10.85	8160
11	19	337	429	0	766	11.41	8740
11	20	14	0	0	14	11.36	159
11	34	62	0	0	62	10.83	671
11	35	62	0	0	62	10.69	663
12	17	209	181	5	395	9.59	3788
12	18	621	307	8	936	10.15	9500
12	19	789	16	0	805	10.23	8235
12	20	654	0	0	654	10.00	6540
12	21	542	0	0	542	10.23	5545
12	22	174	0	0	174	9.75	1696
12	24	425	0	0	425	13.20	5610
12	25	155	34	0	189	10.05	1900
12	26	332	287	0	619	10.19	6308
12	27	262	260	0	522	10.73	5601
12	30	18	0	0	18	10.00	180
13	22	351	0	0	351	11.11	3900
13	23	522	205	0	727	13.26	9640
13	24	75	62	0	137	11.18	1531
13	29	91	7	0	98	10.56	1035
13	30	559	0	0	559	13.56	7580
14	12	213	0	0	213	11.15	2375
14	13	94	14	0	108	10.07	1088
14	21	22	15	1	38	10.96	416
14	22	58	1	0	59	4.07	240
14	23	13	8	0	21	10.26	215
14	28	76	81	0	157	10.66	1673
14	29	261	0	0	261	12.57	3281
15	21	24	14	0	38	10.43	396
15	22	22	16	0	38	11.41	434
15	28	89	68	0	157	9.75	1531
15	29	691	49	0	740	12.35	9139
15	30	92	0	0	92	11.05	1017
15	33	303	0	0	303	11.32	3430
15	34	628	0	0	628	10.02	6293
15	35	463	0	0	463	10.59	4903

ブロック土量一覧表（地山）

[新規業務] 新規備考

B. No	集計範囲(I. J) ~ (I. J)	面積	切土計	盛土計
4	(3, 18) ~ (5, 20)	100	975	
5	(3, 21) ~ (5, 23)	600	7479	
6	(3, 24) ~ (5, 26)	300	1313	
16	(6, 15) ~ (8, 17)	500	5045	
17	(6, 18) ~ (8, 20)	2500	51714	
18	(6, 21) ~ (8, 23)	3600	60260	
19	(6, 24) ~ (8, 26)	3300	17542	3050
20	(6, 27) ~ (8, 29)	1800	914	8473
21	(6, 30) ~ (8, 32)	100	105	
29	(9, 15) ~ (11, 17)	800	5329	352
30	(9, 18) ~ (11, 20)	3400	34453	2369
31	(9, 21) ~ (11, 23)	3600	13252	13665
32	(9, 24) ~ (11, 26)	3600		44279
33	(9, 27) ~ (11, 29)	2900		32340
34	(9, 30) ~ (11, 32)	400	79	120
35	(9, 33) ~ (11, 35)	1200	65	7374
36	(9, 36) ~ (11, 38)	1500		6185
40	(12, 9) ~ (14, 11)	200		210
41	(12, 12) ~ (14, 14)	1300	3699	321
42	(12, 15) ~ (14, 17)	3100	35730	
43	(12, 18) ~ (14, 20)	3600	36630	1466
44	(12, 21) ~ (14, 23)	3600	8704	10223
45	(12, 24) ~ (14, 26)	3600	37961	1291
46	(12, 27) ~ (14, 29)	3100	25959	879
47	(12, 30) ~ (14, 32)	3100	569	34204
48	(12, 33) ~ (14, 35)	3600		63667
49	(12, 36) ~ (14, 38)	2000		16707
53	(15, 9) ~ (17, 11)	400	3381	
54	(15, 12) ~ (17, 14)	3200	44221	
55	(15, 15) ~ (17, 17)	3600	99820	
56	(15, 18) ~ (17, 20)	3600	69615	
57	(15, 21) ~ (17, 23)	3600	48210	
58	(15, 24) ~ (17, 26)	3600	53141	
59	(15, 27) ~ (17, 29)	3600	10311	5784
60	(15, 30) ~ (17, 32)	3600		21679
61	(15, 33) ~ (17, 35)	3600		14965
62	(15, 36) ~ (17, 38)	1600	651	3886
63	(15, 39) ~ (17, 41)	300	2034	
64	(15, 42) ~ (17, 44)	600	8241	
65	(15, 45) ~ (17, 47)	100	1062	
67	(18, 12) ~ (20, 14)	2000	7477	357
68	(18, 15) ~ (20, 17)	3600	37699	
69	(18, 18) ~ (20, 20)	3600	11627	4166
70	(18, 21) ~ (20, 23)	3600	27970	2385
71	(18, 24) ~ (20, 26)	3600	32030	
72	(18, 27) ~ (20, 29)	3600	48	16975
73	(18, 30) ~ (20, 32)	3600		59725
74	(18, 33) ~ (20, 35)	3600		48154
75	(18, 36) ~ (20, 38)	2500	1809	10366
76	(18, 39) ~ (20, 41)	2700	9105	69
77	(18, 42) ~ (20, 44)	3400	17650	3661
78	(18, 45) ~ (20, 47)	400	1068	477
80	(21, 12) ~ (23, 14)	1300	436	175
81	(21, 15) ~ (23, 17)	3000	53	10097
82	(21, 18) ~ (23, 20)	3300		27712

ブロック土量一覧表（地山）

[新規業務] 新規備考

B.No	土 砂	軟 岩 I	軟 岩 II	切 土 計	盛 土	盛 土 計
4	400	575	0	975		
5	3140	2316	2023	7479		
6	1261	52	0	1313		
16	4400	645	0	5045		
17	15708	14520	21486	51714		
18	18838	17896	23526	60260		
19	14242	3300	0	17542	3050	3050
20	909	5	0	914	8473	8473
21	105	0	0	105		
29	4275	1054	0	5329	352	352
30	10897	9477	14079	34453	2369	2369
31	5577	4098	3577	13252	13665	13665
32					44279	44279
33					32340	32340
34	79	0	0	79	120	120
35	65	0	0	65	7374	7374
36					6185	6185
40					210	210
41	1677	1317	705	3699	321	321
42	10300	10278	15152	35730		
43	13707	11307	11616	36630	1466	1466
44	5721	2888	95	8704	10223	10223
45	14740	20931	2290	37961	1291	1291
46	13161	10976	1822	25959	879	879
47	569	0	0	569	34204	34204
48					63667	63667
49					16707	16707
53	2251	1130	0	3381		
54	19691	13496	11034	44221		
55	22880	19541	57399	99820		
56	20261	18267	31087	69615		
57	17844	25567	4799	48210		
58	16182	33324	3635	53141		
59	5317	4456	538	10311	5784	5784
60					21679	21679
61					14965	14965
62	651	0	0	651	3886	3886
63	1396	638	0	2034		
64	3491	4750	0	8241		
65	589	473	0	1062		
67	3387	2500	1590	7477	357	357
68	13198	9784	14717	37699		
69	6109	3512	2006	11627	4166	4166
70	10677	14397	2896	27970	2385	2385
71	14695	16671	664	32030		
72	48	0	0	48	16975	16975
73					59725	59725
74					48154	48154
75	1317	492	0	1809	10366	10366
76	5577	3130	398	9105	69	69
77	8295	8970	385	17650	3661	3661
78	595	473	0	1068	477	477
80	436	0	0	436	175	175
81	53	0	0	53	10097	10097
82					27712	27712

ブロック内運土一覧表（換算）

[新規業務] 新規備考

B. No	土 砂	軟 岩 I	軟 岩 II	切 土 計	距離(m)	仕 事 量
19	2428	622	0	3050	33.77	102999
20	864	5	0	869	40.16	34899
29	277	75	0	352	44.47	15653
30	672	646	1051	2369	43.47	102981
31	5279	4288	4098	13665	42.87	585819
34	75	0	0	75	59.00	4425
35	62	0	0	62	19.63	1217
41	135	117	69	321	37.60	12069
43	499	455	512	1466	43.56	63859
44	5435	3032	109	8576	39.27	336779
45	468	735	88	1291	46.91	60561
46	421	388	70	879	39.52	34738
47	541	0	0	541	40.99	22176
59	2823	2615	346	5784	38.95	225287
62	618	0	0	618	19.07	11785
67	150	122	85	357	37.56	13409
69	2049	1302	815	4166	40.86	170223
70	846	1261	278	2385	40.44	96449
72	46	0	0	46	39.17	1802
75	1251	517	0	1768	46.97	83042
76	40	25	4	69	31.99	2208
77	1626	1944	91	3661	41.90	153396
78	254	223	0	477	49.86	23783
80	175	0	0	175	36.29	6351
81	50	0	0	50	31.20	1560
84	1418	1104	0	2522	40.00	100880
85	2094	37	0	2131	26.29	56024
88	409	235	0	644	43.32	27898
89	1552	225	0	1777	38.66	68698
90	754	0	0	754	31.66	23872
91	110	0	0	110	29.94	3293
95	23	5	0	28	21.97	615
96	2202	1121	309	3632	37.46	136055
97	2235	1771	305	4311	42.76	184339
110	2020	1296	173	3489	41.08	143329
111	5269	1678	0	6947	38.29	266001
112	688	166	0	854	37.30	31854
113	4412	1136	0	5548	38.01	210879
114	1332	0	0	1332	32.28	42997
合計		51602	27146	8403	87151	39.75
距離		38.82	40.76	42.17		

ブロック内運土一覧表（換算）

[新規業務] 新規備考

B. No	X c	Y c	X b	Y b	切土計	距離(m)	仕事量
19	509.363	141.022	514.186	174.449	3050	33.77	102999
20	545.000	135.000	562.960	170.916	869	40.16	34899
29	350.637	190.749	355.000	235.000	352	44.47	15653
30	389.087	193.836	403.531	234.833	2369	43.47	102981
31	439.437	189.142	456.659	228.406	13665	42.87	585819
34	605.000	185.000	644.583	228.750	75	59.00	4425
35	695.000	215.000	696.403	234.582	62	19.63	1217
41	290.133	288.647	255.093	275.000	321	37.60	12069
43	387.557	285.114	404.537	245.000	1466	43.56	63859
44	440.545	285.656	456.440	249.749	8576	39.27	336779
45	514.917	282.366	485.536	245.798	1291	46.91	60561
46	558.730	275.575	593.623	294.140	879	39.52	34738
47	605.000	255.000	638.705	278.319	541	40.99	22176
59	556.759	312.166	572.639	347.732	5784	38.95	225287
62	744.162	334.466	730.348	321.319	618	19.07	11785
67	286.292	371.766	293.166	408.691	357	37.56	13409
69	408.595	376.309	382.092	407.406	4166	40.86	170223
70	450.624	374.010	456.891	413.964	2385	40.44	96449
72	545.000	409.359	578.628	389.271	46	39.17	1802
75	770.762	409.522	727.564	391.091	1768	46.97	83042
76	826.056	387.329	795.000	395.000	69	31.99	2208
77	862.458	374.129	879.408	412.446	3661	41.90	153396
78	905.000	365.141	905.000	415.000	477	49.86	23783
80	263.626	425.357	295.000	443.599	175	36.29	6351
81	315.000	465.000	337.942	443.862	50	31.20	1560
84	505.505	425.237	509.675	465.020	2522	40.00	100880
85	583.814	450.002	558.672	457.678	2131	26.29	56024
88	774.133	427.115	743.911	458.148	644	43.32	27898
89	807.590	436.328	788.750	470.090	1777	38.66	68698
90	890.889	458.495	874.579	431.357	754	31.66	23872
91	905.000	454.943	905.000	425.000	110	29.94	3293
95	397.719	498.569	415.000	485.000	28	21.97	615
96	464.090	528.513	458.224	491.513	3632	37.46	136055
97	492.659	533.259	512.859	495.567	4311	42.76	184339
110	491.492	551.545	532.370	555.578	3489	41.08	143329
111	574.996	583.783	563.413	547.282	6947	38.29	266001
112	645.266	592.088	637.132	555.683	854	37.30	31854
113	692.471	586.989	682.040	550.437	5548	38.01	210879
114	729.413	575.493	742.368	545.922	1332	32.28	42997
合計						87151	39.75

ブロック間手動運土一覧表（換算）

GROUP: 1 [新規業務] 新規備考

切土	盛土	土 砂	軟 岩 I	軟 岩 II	切 土 計	距離(m)	仕 事 量
19	20	7597	0	0	7597	61.37	466228
19	33	3505	2843	0	6348	81.49	517298
5	33	2983	2432	2326	7741	146.37	1133051
4	33	380	604	0	984	171.24	168500
18	33	17237	0	0	17237	130.25	2245119
18	32	659	18791	24787	44237	91.76	4059187
91	90	994	0	0	994	38.49	38259
78	90	311	274	0	585	72.87	42629
65	90	560	497	0	1057	82.19	86874
64	90	1348	0	0	1348	76.50	103122
41	40	210	0	0	210	57.27	12027
94	81	200	0	0	200	70.02	14004
128	115	5	0	0	5	56.00	280
127	115	5	0	0	5	58.47	292
126	113	1853	609	0	2462	54.89	135139
125	113	1672	392	0	2064	65.26	134697
124	112	1944	0	0	1944	83.52	162363
111	112	1116	356	0	1472	68.19	100376
109	96	7079	2391	0	9470	64.45	610342
109	97	0	243	324	567	79.14	44872
110	97	1758	1128	151	3037	59.92	181977
合計		51416	30560	27588	109564	93.61	10256636

ブロック間手動運土一覧表（換算）

GROUP: 1 [新規業務] 新規備考

切土	盛土	土 砂	軟岩 I	軟岩 II	切土計	距離(m)	仕事量
91	90	994	0	0	994	38.49	38259
50.0 m 未満の合計							
小計		994	0	0	994	38.49	38259
距離		38.49	0.00	0.00			
19	20	7597	0	0	7597	61.37	466228
19	33	3505	2843	0	6348	81.49	517298
18	32	659	18791	24787	44237	91.76	4059187
78	90	311	274	0	585	72.87	42629
65	90	560	497	0	1057	82.19	86874
64	90	1348	0	0	1348	76.50	103122
41	40	210	0	0	210	57.27	12027
94	81	200	0	0	200	70.02	14004
128	115	5	0	0	5	56.00	280
127	115	5	0	0	5	58.47	292
126	113	1853	609	0	2462	54.89	135139
125	113	1672	392	0	2064	65.26	134697
124	112	1944	0	0	1944	83.52	162363
111	112	1116	356	0	1472	68.19	100376
109	96	7079	2391	0	9470	64.45	610342
109	97	0	243	324	567	79.14	44872
110	97	1758	1128	151	3037	59.92	181977
100.0 m 未満の合計							
小計		29822	27524	25262	82608	80.76	6671707
距離		67.79	85.05	91.41			
5	33	2983	2432	2326	7741	146.37	1133051
18	33	17237	0	0	17237	130.25	2245119
150.0 m 未満の合計							
小計		20220	2432	2326	24978	135.25	3378170
距離		132.63	146.37	146.37			
4	33	380	604	0	984	171.24	168500
200.0 m 未満の合計							
小計		380	604	0	984	171.24	168500
距離		171.24	171.24	0.00			
合計		51416	30560	27588	109564	93.61	10256636
距離		93.49	91.63	96.04			

ブロック間自動運土一覧表（換算）

[新規業務]		新規備考						
切土	盛土	土 砂	軟 岩 I	軟 岩 II	切土計	距離(m)	仕事量	
46	47	12082	11137	2025	25244	80.02	2020025	
59	60	1984	1838	243	4065	77.83	316380	
67	81	2632	2148	1495	6275	88.69	556530	
68	82	8408	6889	11350	26647	90.64	2415284	
69	83	3755	2386	1492	7633	97.70	745744	
71	84	9222	11564	505	21291	75.36	1604490	
80	81	239	0	0	239	76.59	18305	
89	101	2020	292	0	2312	93.99	217305	
100.0 m 未満の合計								
小計		40342	36254	17110	93706	84.24	7894063	
距離		83.95	82.23	89.20				
29	44	1292	353	0	1645	121.14	199275	
45	47	549	861	103	1513	123.85	187386	
45	60	6380	10014	1200	17594	126.78	2230567	
53	81	2138	1186	0	3324	149.60	497271	
56	83	2701	2691	5017	10409	149.25	1553543	
58	72	4767	10850	1296	16913	123.79	2093661	
67	82	436	355	248	1039	130.86	135963	
76	101	5258	3261	454	8973	144.09	1292919	
150.0 m 未満の合計								
小計		23521	29571	8318	61410	133.38	8190585	
距離		134.40	130.45	140.90				
45	61	5422	8510	1019	14951	184.45	2757713	
55	83	4540	4286	13789	22615	174.36	3943151	
58	73	10606	24140	2884	37630	158.29	5956453	
59	75	244	226	30	500	188.16	94080	
63	101	1326	670	0	1996	173.46	346226	
64	101	1968	4987	0	6955	196.30	1365266	
71	73	2237	2806	122	5165	196.60	1015439	
77	101	2363	2823	133	5319	176.93	941091	
77	102	3230	3861	182	7273	155.10	1128042	
77	115	661	790	37	1488	189.51	281991	
200.0 m 未満の合計								
小計		32597	53099	18196	103892	171.62	17829452	
距離		172.31	170.92	172.41				
45	62	1184	1858	223	3265	218.92	714773	
57	73	5800	9186	1888	16874	207.42	3500005	
57	86	4490	7110	1462	13062	249.22	3255312	
71	74	2493	3125	137	5755	245.10	1410551	
95	112	1117	221	0	1338	246.13	329322	
250.0 m 未満の合計								
小計		15084	21500	3710	40294	228.57	9209963	
距離		229.86	228.11	225.97				
6	34	43	2	0	45	256.06	11523	
6	35	1069	49	0	1118	288.63	322688	
6	48	43	2	0	45	280.77	12635	
18	35	0	0	1921	1921	294.73	566176	
21	36	100	0	0	100	285.16	28516	
30	47	1050	1010	1643	3703	263.53	975851	
55	97	909	858	2761	4528	270.55	1225051	
57	74	3497	5538	1139	10174	255.92	2603730	
68	85	246	202	333	781	291.50	227662	
68	98	3884	3182	5242	12308	287.74	3541504	
70	99	9297	13856	3052	26205	283.05	7417326	
300.0 m 未満の合計								
小計		20138	24699	16091	60928	277.91	16932662	
距離		278.01	276.42	280.09				
6	36	43	2	0	45	331.92	14937	
17	35	480	490	794	1764	326.14	575311	
17	48	8468	8650	14021	31139	318.28	9910921	

ブロック間自動運土一覧表（換算）

[新規業務]		新規備考						
切土	盛土	土 砂	軟 岩 I	軟 岩 II	切 土 計	距離(m)	仕 事 量	
18	36	0	0	302	302	338.02	102082	
18	49	0	0	45	45	328.77	14795	
29	47	2492	679	0	3171	301.08	954724	
30	35	603	580	943	2126	319.48	679214	
30	48	7951	7642	12436	28029	311.62	8734397	
31	36	19	15	15	49	318.32	15598	
43	74	3532	3220	3623	10375	330.41	3428003	
54	97	4313	3267	2926	10506	303.40	3187520	
55	85	1406	1328	4271	7005	329.54	2308427	
55	98	3681	3475	11179	18335	325.78	5973177	
56	86	4027	4013	7479	15519	340.16	5278943	
57	87	1658	2625	539	4822	324.82	1566282	
57	88	1283	2032	418	3733	337.26	1258992	
71	88	8	10	0	18	326.44	5876	
350.0 m 未満の合計								
小計		39964	38028	58991	136983	321.27	44009199	
距離		319.65	321.36	322.32				
16	35	324	52	0	376	363.86	136812	
16	48	3781	613	0	4394	356.00	1564264	
17	36	1449	1481	2399	5329	369.43	1968693	
17	49	4526	4625	7495	16646	360.18	5995556	
30	36	76	73	118	267	362.77	96860	
42	74	5614	6192	9999	21805	384.73	8389037	
42	86	388	427	690	1505	378.03	568936	
43	75	974	887	999	2860	363.58	1039838	
43	87	418	381	428	1227	399.31	489954	
54	85	468	355	317	1140	362.38	413113	
54	98	6730	5099	4565	16394	358.62	5879216	
55	112	1616	1525	4908	8049	398.02	3203662	
57	101	224	354	73	651	379.04	246755	
400.0 m 未満の合計								
小計		26588	22064	31991	80643	371.92	29992696	
距離		368.43	371.34	375.22				
16	36	75	12	0	87	407.15	35422	
42	75	508	561	905	1974	417.90	824935	
43	88	3357	3061	3443	9861	411.75	4060267	
54	99	6064	4593	4113	14770	414.80	6126595	
54	112	106	80	72	258	430.86	111162	
55	100	8954	8451	27189	44594	446.31	19902749	
55	113	405	383	1230	2018	440.32	888567	
56	87	8390	8361	15583	32334	415.76	13443183	
56	88	4130	4115	7671	15916	428.20	6815231	
450.0 m 未満の合計								
小計		31989	29617	60206	121812	428.60	52208111	
距離		425.69	426.04	431.40				
41	75	1248	1266	742	3256	460.79	1500332	
42	87	204	226	364	794	453.63	360182	
42	88	839	926	1494	3259	466.07	1518923	
43	101	4242	3868	4353	12463	453.53	5652344	
54	100	818	620	555	1993	479.16	954966	
54	113	106	80	72	258	473.17	122078	
55	114	225	212	682	1119	499.04	558425	
500.0 m 未満の合計								
小計		7682	7198	8262	23142	460.95	10667250	
距離		460.41	460.19	462.10				
42	101	2232	2460	3973	8665	507.85	4400520	
54	114	101	77	69	247	531.88	131375	
500.0 m 以上の合計								
小計		2333	2537	4042	8912	508.52	4531895	
距離		508.89	508.58	508.26				
合計		240238	264567	226917	731722	275.33	201465876	
距離		258.67	246.74	326.30				

ブロック間自動運土一覧表（換算）

[新規業務] 新規備考

切土	盛土	土 砂	軟 岩 I	軟 岩 II	切 土 計	距離(m)	仕 事 量
80	81	239	0	0	239	76.59	18305
-30.0 % 未満の合計							
小計		239	0	0	239	76.59	18305
距離		76.59	0.00	0.00			
29	44	1292	353	0	1645	121.14	199275
71	84	9222	11564	505	21291	75.36	1604490
-20.0 % 未満の合計							
小計		10514	11917	505	22936	78.64	1803765
距離		80.99	76.72	75.36			
46	47	12082	11137	2025	25244	80.02	2020025
53	81	2138	1186	0	3324	149.60	497271
67	81	2632	2148	1495	6275	88.69	556530
68	82	8408	6889	11350	26647	90.64	2415284
69	83	3755	2386	1492	7633	97.70	745744
-15.0 % 未満の合計							
小計		29015	23746	16362	69123	90.20	6234854
距離		91.30	89.14	89.79			
16	35	324	52	0	376	363.86	136812
16	36	75	12	0	87	407.15	35422
18	36	0	0	302	302	338.02	102082
31	36	19	15	15	49	318.32	15598
45	47	549	861	103	1513	123.85	187386
45	60	6380	10014	1200	17594	126.78	2230567
54	97	4313	3267	2926	10506	303.40	3187520
55	83	4540	4286	13789	22615	174.36	3943151
55	97	909	858	2761	4528	270.55	1225051
56	83	2701	2691	5017	10409	149.25	1553543
58	72	4767	10850	1296	16913	123.79	2093661
58	73	10606	24140	2884	37630	158.29	5956453
59	60	1984	1838	243	4065	77.83	316380
67	82	436	355	248	1039	130.86	135963
-10.0 % 未満の合計							
小計		37603	59239	30784	127626	165.48	21119589
距離		166.50	154.14	186.07			
6	35	1069	49	0	1118	288.63	322688
6	36	43	2	0	45	331.92	14937
6	48	43	2	0	45	280.77	12635
16	48	3781	613	0	4394	356.00	1564264
17	35	480	490	794	1764	326.14	575311
17	36	1449	1481	2399	5329	369.43	1968693
17	48	8468	8650	14021	31139	318.28	9910921
17	49	4526	4625	7495	16646	360.18	5995556
18	35	0	0	1921	1921	294.73	566176
18	49	0	0	45	45	328.77	14795
29	47	2492	679	0	3171	301.08	954724
30	35	603	580	943	2126	319.48	679214
30	36	76	73	118	267	362.77	96860
30	47	1050	1010	1643	3703	263.53	975851
30	48	7951	7642	12436	28029	311.62	8734397
42	86	388	427	690	1505	378.03	568936
42	87	204	226	364	794	453.63	360182
42	88	839	926	1494	3259	466.07	1518923
42	101	2232	2460	3973	8665	507.85	4400520
43	74	3532	3220	3623	10375	330.41	3428003
43	75	974	887	999	2860	363.58	1039838
43	87	418	381	428	1227	399.31	489954
43	88	3357	3061	3443	9861	411.75	4060267
43	101	4242	3868	4353	12463	453.53	5652344
45	61	5422	8510	1019	14951	184.45	2757713
45	62	1184	1858	223	3265	218.92	714773

ブロック間自動運土一覧表（換算）

[新規業務]		新規備考						
切土	盛土	土 砂	軟 岩 I	軟 岩 II	切 土 計	距離(m)	仕 事 量	
54	85	468	355	317	1140	362.38	413113	
54	98	6730	5099	4565	16394	358.62	5879216	
54	99	6064	4593	4113	14770	414.80	6126595	
54	100	818	620	555	1993	479.16	954966	
54	112	106	80	72	258	430.86	111162	
54	113	106	80	72	258	473.17	122078	
54	114	101	77	69	247	531.88	131375	
55	85	1406	1328	4271	7005	329.54	2308427	
55	98	3681	3475	11179	18335	325.78	5973177	
55	100	8954	8451	27189	44594	446.31	19902749	
55	112	1616	1525	4908	8049	398.02	3203662	
55	113	405	383	1230	2018	440.32	888567	
55	114	225	212	682	1119	499.04	558425	
56	86	4027	4013	7479	15519	340.16	5278943	
56	87	8390	8361	15583	32334	415.76	13443183	
56	88	4130	4115	7671	15916	428.20	6815231	
57	73	5800	9186	1888	16874	207.42	3500005	
57	74	3497	5538	1139	10174	255.92	2603730	
57	86	4490	7110	1462	13062	249.22	3255312	
57	87	1658	2625	539	4822	324.82	1566282	
57	88	1283	2032	418	3733	337.26	1258992	
57	101	224	354	73	651	379.04	246755	
59	75	244	226	30	500	188.16	94080	
63	101	1326	670	0	1996	173.46	346226	
68	85	246	202	333	781	291.50	227662	
68	98	3884	3182	5242	12308	287.74	3541504	
70	99	9297	13856	3052	26205	283.05	7417326	
71	73	2237	2806	122	5165	196.60	1015439	
71	74	2493	3125	137	5755	245.10	1410551	
71	88	8	10	0	18	326.44	5876	
77	102	3230	3861	182	7273	155.10	1128042	
95	112	1117	221	0	1338	246.13	329322	
-5.0 % 未満の合計								
小計		143084	149491	166996	459571	342.57	157436448	
距離		331.96	319.70	372.14				
6	34	43	2	0	45	256.06	11523	
21	36	100	0	0	100	285.16	28516	
41	75	1248	1266	742	3256	460.79	1500332	
42	74	5614	6192	9999	21805	384.73	8389037	
42	75	508	561	905	1974	417.90	824935	
64	101	1968	4987	0	6955	196.30	1365266	
76	101	5258	3261	454	8973	144.09	1292919	
77	101	2363	2823	133	5319	176.93	941091	
77	115	661	790	37	1488	189.51	281991	
0.0 % 未満の合計								
小計		17763	19882	12270	49915	293.21	14635610	
距離		263.13	266.50	380.03				
89	101	2020	292	0	2312	93.99	217305	
15.0 % 未満の合計								
小計		2020	292	0	2312	93.99	217305	
距離		93.99	93.99	0.00				
合計		240238	264567	226917	731722	275.33	201465876	
距離		258.67	246.74	326.30				

土質別地山換算土量計算書

[新規業務] 新規備考

項目	土 砂	軟 岩 I	軟 岩 II	切 土 計	運搬距離
メッシュ内運土	50905	9827	515	61247	10.72
ブロック内運土	51527	27146	8403	87076	39.73
ブロック間手動運土	994	0	0	994	38.49
50.0 m 未満の合計					
換算土量-小計	103426	36973	8918	149317	27.83
地山変換した土量	108869	35212	7755	151836	
補正土量-地山	-5	-1	0	-6	
決定土量-地山	108864	35211	7755	151830	
ブロック内運土	75	0	0	75	59.00
ブロック間自動運土	40342	36254	17110	93706	84.24
ブロック間手動運土	29822	27524	25262	82608	80.76
100.0 m 未満の合計					
換算土量-小計	70239	63778	42372	176389	82.60
地山変換した土量	73936	60741	36845	171522	
補正土量-地山	-3	-2	-1	-6	
決定土量-地山	73933	60739	36844	171516	
ブロック間自動運土	23521	29571	8318	61410	133.38
ブロック間手動運土	20220	2432	2326	24978	135.25
150.0 m 未満の合計					
換算土量-小計	43741	32003	10644	86388	133.92
地山変換した土量	46043	30479	9256	85778	
補正土量-地山	-2	-1	0	-3	
決定土量-地山	46041	30478	9256	85775	
ブロック間自動運土	32597	53099	18196	103892	171.62
ブロック間手動運土	380	604	0	984	171.24
200.0 m 未満の合計					
換算土量-小計	32977	53703	18196	104876	171.61
地山変換した土量	34713	51146	15823	101682	
補正土量-地山	-1	-1	0	-2	
決定土量-地山	34712	51145	15823	101680	
ブロック間自動運土	15084	21500	3710	40294	228.57
250.0 m 未満の合計					
換算土量-小計	15084	21500	3710	40294	228.57
地山変換した土量	15878	20476	3226	39580	
補正土量-地山	-1	-1	0	-2	
決定土量-地山	15877	20475	3226	39578	
ブロック間自動運土	20138	24699	16091	60928	277.91
300.0 m 未満の合計					
換算土量-小計	20138	24699	16091	60928	277.91
地山変換した土量	21198	23523	13992	58713	
補正土量-地山	-1	-1	0	-2	
決定土量-地山	21197	23522	13992	58711	
ブロック間自動運土	39964	38028	58991	136983	321.27
350.0 m 未満の合計					
換算土量-小計	39964	38028	58991	136983	321.27
地山変換した土量	42067	36217	51297	129581	
補正土量-地山	-2	-1	-1	-4	
決定土量-地山	42065	36216	51296	129577	
ブロック間自動運土	26588	22064	31991	80643	371.92
400.0 m 未満の合計					
換算土量-小計	26588	22064	31991	80643	371.92
地山変換した土量	27987	21013	27818	76818	
補正土量-地山	-1	0	-1	-2	
決定土量-地山	27986	21013	27817	76816	
ブロック間自動運土	31989	29617	60206	121812	428.60

土質別地山換算土量計算書

[新規業務] 新規備考

項目	土 砂	軟 岩 I	軟 岩 II	切 土 計	運搬距離
450.0 m 未満の合計					
換算土量－小計	31989	29617	60206	121812	428.60
地山変換した土量	33673	28207	52353	114233	
補正土量－地山	-2	-1	-1	-4	
決定土量－地山	33671	28206	52352	114229	
ブロック間自動運土	7682	7198	8262	23142	460.95
500.0 m 未満の合計					
換算土量－小計	7682	7198	8262	23142	460.95
地山変換した土量	8086	6855	7184	22125	
補正土量－地山	0	0	0	0	
決定土量－地山	8086	6855	7184	22125	
ブロック間自動運土	2333	2537	4042	8912	508.52
500.0 m 以上の合計					
換算土量－小計	2333	2537	4042	8912	508.52
地山変換した土量	2456	2416	3515	8387	
補正土量－地山	0	0	0	0	
決定土量－地山	2456	2416	3515	8387	
換算土量－合計	394161	332100	263423	989684	
地山変換した土量	414906	316285	229064	960255	
補正土量－地山	-18	-9	-4	-31	
決定土量－地山	414888	316276	229060	960224	

工区間自動運土一覽表（換算）

[新規業務] 新規備考

工区	切土	工区	盛土	土 砂	切土計	距離(m)	仕事量
1	H 1	15	S 6	48841	48841	100.00	4884100
1	H 1	16	S 7	16753	16753	50.00	837650
2	H 2	15	S 6	83278	83278	120.00	9993360
3	H 3	16	S 7	110804	110804	60.00	6648240
4	H 4	5	S 1	77982	77982	10.00	779820
4	H 4	15	S 6	14522	14522	100.00	1452200
6	H 5	15	S 6	21367	21367	140.00	2991380
7	H 6	15	S 6	86478	86478	140.00	12106920
9	H 7	8	S 2	47614	47614	40.00	1904560
9	H 7	11	S 3	30349	30349	60.00	1820940
10	H 8	11	S 3	4799	4799	50.00	239950
14	H 9	15	S 6	56456	56456	60.00	3387360
17	H 10	12	S 4	90848	90848	30.00	2725440
17	H 10	13	S 5	12176	12176	30.00	365280
取	B 1	11	S 3	2394	2394	200.00	478800
取	B 1	13	S 5	57286	57286	200.00	11457200
取	B 1	15	S 6	12711	12711	250.00	3177750
合計				774658	774658	84.23	65250950